

224
R

1-21-88

6031031

API NUMBER 15-195-21948-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SE, SEC. 3, T 14 S, R 22 W/E

330 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6111

Lease Name Fabrizius Well # 1

Operator: Emphasis Oil Operations

County Trego 141.51

Name & Address Box 819

Well Total Depth 4354 feet

Russell, Ks. 67665

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: AM Day: 21 Month: 1 Year: 19 88

Plugging proposal received from Ronnie

(company name) Kelso (phone) _____

were: 8 5/8 set at 264 ft. with 150 sx cwc 4 1/2 set at 4350 ft. with 125 sx port collar set at any 1600+ PBD 4183 Perf 4168-74 order sand and com. cmt.

pull pipe order 200 sx ATL cement blend 65/35 poz 10% gel 2% Dicel 500 # hulls

Allied Cmt. Co. Sundowner Water Truck

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 PM Day: 21 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 4115' with 4 sx com. cmt. on sand with bailer

one shot at 3327' recovered same

squeeze 8 5/8 with 200 sx ATL cement blend with 500 # hulls mixed in.

Max. PSI 500 # close in PSI 200 # plug complete.

STATE CORPORATION COMMISSION

FEB 05 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
DO NOT DESTROY preserve this plugging.

DATE 2-8-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 19766

Carl Goodrow