

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21618-00-00
Spot: CSESESW Sec/Twnshp/Rge: 3-14S-22W
330 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: FABRIZIUS Well Number: 1
County: TREGO Total Vertical Depth: 4300 feet

Operator License No.: 31341
Op Name: CRAIG, WARD DBA CRAIG OIL COMPA
Address: 48 SOUTH KANSAS
RUSSELL, KS 67665

Production Casing Size: 4.5 feet: 4299 100 SX CMT
Surface Casing Size: 8.625 feet: 266 225 SX CMT

\$139.75

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/10/2003 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: WARD CRAIG Company: CRAIG OIL COMPANY Phone: (785) 483-1543

Proposed Plugging Method: Ordered 200 sxs cement - 500# hulls - 14 sxs gel.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/10/2003 11:40 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 266' w/225 sxs cement. 4 1/2" casing at 4299' w/100 sxs cement.
D.V. at 1800' to surface with 350 sxs cement.
Tied to 4 1/2" and 40 sxs cement with 250# hulls - 14 sxs gel with 250# hulls and 100 sxs cement.
Max. P.S.I. 1400#. S.I.P. 1000#.
Tied to annulus - pressured immediately - took no cement.
Total of 140 sxs 60/40 pozmix - 10% gel - 14 sxs gel - 500# hulls.
Dakota 548' - 848'. Anhydrite 1747' - 1787'. Salt 2150' - 2322'.

RECEIVED
APR 18 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. HONAS TANK-WATER.

Plugged through: CSG

District: 04

100 Signed Roger Moses
(TECHNICIAN)

INVOICED

DATE 4-21-03

INV NO 2003061425

APR 15 2003

ZENITH DRILLING CORPORATION
 FOURTH FINANCIAL CENTER, #505 #1 FABRIZIOUS 3-14-22W
 WICHITA, KS 67202 SE SE SW

CONTR D&B DRILLING, INC. CTY TREGO
 GEOL GERALD BECKER FIELD WC (CEDAR VIEW WEST DISC)
 ELV 2303 KB SPD 11/6/84 CARD ISSUED 4/4/85 IP P 86° 00' A 124' BWPD
2298 GL DRLG COMP 11/13/84 CHER 4171-4172

LOG	Tops	Depth/Datum
ANH	1747 + 556
TOP	3430-1127
HEEB	3682-1379
LANS	3716-1413
BKC	3968-1665
CHER SH	4118-1815
CHER SD	4170-1867
MISS	4260-1957
RTD	4300-1997

AP 15-195-21,618
 8-5/8" 266 / 225SX 1 1/2" 4299 / 100SX
 DST (1) 4123-80 (CHER SH) / 30-45-30-60-300 GIP REC 1730
 G&HOCW, SIP 1056-1056# RP 219-4717-580-721#
 MICT - CO, PF (CHER SD) 4171-72 W 7/4 SPF SWB DWN NAT
 SET 2-7/8 TBG AT 4162 POP P 86° 00' A 124' BWPD (GR 35)

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS