

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-23, 236 0000

NE 1/4 Sec. 15, T 19 S, R 15 W/E

330 feet from (N)S section line

990 feet from (W)E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6278

Lease Name TRESTER Well # 1

Operator: PETX PETROLEUM CORP.
Name & Address 1616 GLENARM PLACE #1700
DENVER, COLORADO
80202

County BARTON

Well Total Depth 3596 feet # 116.87

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 380

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor H-30 INC License Number TAG # 1 5130

Address 251 N. WINTER #10 WICHITA, KS. 67202

Company to plug at: Hour: 3:45 AM Day: 11 Month: NOV. Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO DICK DAVIS

(company name) H-30 INC (phone) 303-629-1098

were: 8 5/8 - 380 FT SR. CMC #200 SK 60 1/40 Formix 2% GEL-3% CA-CL (ALLIED)
ORDER 200 SK 50 1/50 Formix 4% GEL-3% CA-CL. AND 8 5/8" PLUG
SPOT WITH DRILL STEM-TURN HOLE OVER - HEAVY MUD BETWEEN PLUGS
ABRUABLE @ 3507 FT

Signed Mason Schmidt
(TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:45 AM Day: 11 Month: NOV. Year: 1983

ACTUAL PLUGGING REPORT

ORDERED-200 SK 50 1/50 Formix 4% GEL-3% CA-CL. AND 8 5/8" PLUG
SPOTTED WITH DRILL STEM-TURNED HOLE OVER - HEAVY MUD BETWEEN PLUGS.
1ST Plug @ 3480 FT #20 SK CMT. - 2ND Plug @ 1020 FT #20 SK CMT
3RD Plug @ 630 FT #100 CMT #1 SK CELLO FLOOR FLAME - 4TH PLUG @ 240 FT #20 SK CMT.
5TH Plug ^{SOLID BRIDGE} HULL'S-PLUG @ 40 FT #10 SK CMT., 10 SK IN BAT HOLE.

Remarks: CEMENTED BY ALLIED CMT.

I hereby certify that the above plugging instructions were given as herein stated and that I ~~did~~ / did not observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1983

INVOICED
CONSERVATION DIVISION
Wichita, Kansas

DATE 12-27-83

INV. NO. 7207-W

Signed Mason Schmidt
(TECHNICIAN) DOIC