

4-060679

4-25

15-009-30356-0000

API number: 15- - 1-27-66

NW NE SW /4 SEC. 14, 17 S, 15 W
2310 feet from S section line
3630 feet from E section line

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

Operator license# 30742 Lease Benedict Axman well # 1

Operator: Palomino Petroleum, Inc. County Barton 114.30

Address: 4924 SE 84th Street Well total depth 3517 feet
Newton, Kansas 67114-8827 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 996 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: D.S. & W. Well Servicing, Inc. License# 6901

Address: Claflin, Kansas 67525

Company to plug at: Hour: 10:00A.M. Day: 25 Month: April Year: 95

Plugging proposal received from: Kevin Strube

Company: D.S. & W. Well Servicing, Inc. Phone: 316-587-3361

Were: Order 275 sxs. 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

RECEIVED
KANSAS CORPORATION COMMISSION
APR 28 1995
CONSERVATION DIVISION
WICHITA, KS


Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 11:15A.M., Day: 25, Month: April, Year: 95

Actual plugging report: 8 5/8" to 996' w/400 sxs. 5 1/2" to 3510' w/125 sxs.
Sanded to 3440' and spotted 5 sxs. cement with dump bailer. Cut casing at
1916' and pulled to 1752'. Mixed and pumped 120 sxs. cement with 300# hulls.
Pulled casing to 1025' and pumped 40 sxs. cement. Pulled casing to 525' and
circulated cement with 115 sxs. Pulled casing with cement in cellar.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X / did not observe the plugging.


(agent)
1041

INVOICED
DATE 5-5-95
INV. NO. 42765