

5-17-88

320

API NUMBER 15-009-30257-0000

SW , SEC. 11, T 17 S, R 15 (W/E)
1650 feet from S section line

4290 feet from E section line

Lease Name Max Mater Well # 2

County Barton 113.88

Well Total Depth 3504 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 990

To: 6 061492
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3646

Operator: Haven Energy Corp.

Name & Address 7310 East Kelllogg

Wichita, Ks. 67207.

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 8:00A. Day: 17 Month: May Year: 1988

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone)

were: Order 125 sks 65/35 Pozmix 10% Gel 2% Econolite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00AM Day: 17 Month: May Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 990' w/400 sks. 5 1/2" set at 3501' w/125 sks.

Open hole 3' Plugged bottom w/sand and 5 sks cement to 3450'. Shot pipe one time and recovered 2800'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 100 sks cement w/900 Psi.

RECEIVED

Remarks: By Hall STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-22-88

INV. NO. 20925

06-01-88
CONSERVATION DIVISION
Wichita, Kansas

Signed Gilbert G. Scheck
(TECHNICIAN)
Gilbert G. Scheck