

5-17-88 319

To: 6 061491  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-009-30256-0000 R

SW, SEC. 11, T 17 S, R 15 (W)  
2310 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3646

Lease Name Mater Well # 1

Operator: Haven Energy Corp  
Name & Address: 7310 East Kellogg  
Wichita, Ks. 67207

County Barton 114.37  
Well Total Depth 3519 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 981

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ U&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 8:00 AM Day: 17 Month: May Year: 19 88

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) \_\_\_\_\_

were: Order 125 sks 65/35 Poz 10% Gel 2% Econolite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45AM Day: 17 Month: May Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 981' w/400 sks. 4 1/2" set at 3470' w/125 sks.

Top perf at 3239'. Plugged bottom w/sand and 4 sks cement to 3175'. Shot pipe two times and recovered 2631'. Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 100 sks cement w/900 Psi.

RECEIVED

By Hall STATE CORPORATION COMMISSION

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 6-22-88  
INV. NO. 20924  
JUN - 1 1988  
06-01-88  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Gilbert G. Scheck (TECHNICIAN)  
Gilbert Scheck

FORM CP-2/3  
Rev. 01-84