

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-199-20424-00-00
Spot: NESESESW Sec/Twnshp/Rge: 5-15S-41W
337 feet from S Section Line, 2600 feet from W Section Line
Lease Name: FLYING V Well #: 3-5
County: WALLACE Total Vertical Depth: 2070 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	443		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/07/2014 3:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: CECIL O'BRATE Company: AMERICAN WARRIOR INC. Phone: (620) 275-2963

Proposed Plugging Method: 8 5/8" surface casing set at 443' w/600 sx cement.
Drilled to 2070' and lost circulation. Operator decided to plug and skid rig.
Ordered 230 sx 60/40 pozmix 4% gel cement, 12 sx calcium chloride and 500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/30/2014 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran drill pipe to 2000'. Pumped 25 sx cement 3% c.c. and 100 # hulls. Pulled drill pipe to 1675' and pumped 35 bbls drilling mud. Pumped 100 sx cement w/3% c.c. and 300 # hulls. Returns near end of displacement. Pulled drill pipe to 500' and pumped 35 bbls drilling mud. Pumped 50 sx 3% c.c. and 100 # hulls. Lost circulation immediately after pumping ceased. Omitted final plug due to cement dropping in casing. Rathole plugged w/30 sx cement. Plugged mousehole w/15 sx cement. Surface casing capped. Drilling rig to be moved 50' west of well. Cement level to be measured after drilling equipment moved. Plug to be finished with pulling unit. (Joe Smith)
10/29/2014- Ran tubing to tag cement at 645'. Pumped 200 sx cement w/500 # hulls. Good circulation for 150 sx cement. Lost circulation. Pulled tubing from well.
10/30/2014- Tagged cement with tubing at 271'. Pulled tubing from well.
10/30/2014- Halde Redi-Mix Inc. filled 8 5/8' surface casing to surface w/100 sx neat cement.

GPS: 38.77152 -101.90032

Perfs:

Received
KANSAS CORPORATION COMMISSION
NOV 14 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: 10/07/14- ALLIED CEMENT TICKET # 55514. 10/29/14- ALLIED CEMENT TICKET # 64,217. 10/30/14- HALDE REDI-MIX INC. TICKET # 19,658

Plugged through: TBG

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CM

CKM 11/25/14

NOV 06 2014

Form CP-2/3