

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-20941-00-00  
Spot: SESW Sec/Twnshp/Rge: 20-22S-33W  
660 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: FRANCES Well #: 3-20  
County: FINNEY Total Vertical Depth: 4899 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4899	1760	WITH 400 SX CMT
SURF	8.625	1656		WITH 600 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/28/2014 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: WAYNE GERSTNER Company: BEREXCO Phone: (620) 275-0320

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/28/2014 4:45 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET 50 SX CMT PLUG FROM 4191' TO 3783' ON 3/25/14. WAITED 2 HOURS. TAGGED PLUG AT 3783'. 1ST PLUG AT 1730' WITH 15 SX GEL & 200# HULLS THEN 50 SX CMT & 200# HULLS. 2ND PLUG AT 1100' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 15 SX CMT. CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4780	4784		
4756	4762		
4720	4726		
4434	4440		
4366	4372		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Larry Harris  
(TECHNICIAN)

RECEIVED  
NOV - 6 2014  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION  
NOV 17 2014  
CONSERVATION DIVISION  
WICHITA, KS

11-25-14 CKM