

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21690-00-00
Spot: NESWNE Sec/Twnshp/Rge: 15-28S-7E
3932 feet from S Section Line, 1773 feet from E Section Line
Lease Name: KORTE Well #: 1
County: BUTLER Total Vertical Depth: 2784 feet

Operator License No.: 31074
Op Name: BRAKE, JOE DBA BRAKE INC.
Address: RT 1 BOX 84
LATHAM, KS 67072

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2783		120 SX
SURF	8.625	120		110 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/28/2014 8:00 AM
Plug Co. License No.: 31074 Plug Co. Name: BRAKE, JOE DBA BRAKE INC.
Proposal Rcvd. from: JOE BRAKE Company: JOE BRAKE/BRAKE INC. Phone: (620) 965-2297

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 08/28/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SHOT SQUEEZE HOLES @ 2765' - 2766' (2 HOLES). RIH W/TBG @ 2714'. ELITE CEMENTING MIXED & PUMPED 25 SXS CLASS A COMMON 3% CC & DISPLACED IN CSG. SHOT TUBING OFF IN WELL @ 2592', LAYED DOWN TUBING RIH ON WIRELINE SHOT SQUEEZE HOLES @ 250'-251' (2 SHOTS). RIH W/TBG @ 270', ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED & PUMPED 85 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCUALTED. ELITE CEMENT TICKET #S 1640. 8-29-2014, TAGGED CEMENT @ SURFACE.

Perfs:

Top	Bot	Thru	Comments
2734	2735	CSG	

Received
KANSAS CORPORATION COMMISSION

Remarks: COMPLIANCE PLUGGING

Plugged through: TBG

NOV 12 2014
CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed DUANE KRUEGER
11-25-14 CKM (TECHNICIAN)