

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-20236-00-00
Spot: SW Sec/Twnshp/Rge: 15-24S-31W
1370 feet from S Section Line, 1270 feet from W Section Line
Lease Name: KISNER Well #: 1-15
County: FINNEY Total Vertical Depth: 2900 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2719	0	WITH 500 SX CMT
SURF	8.625	350		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/04/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 250# HULLS & 150 SX CMT DOWN 4 1/2" CASING. DISPLACE WITH WATER TO 1150'. RUN CBL. PERFORATE AND/OR RUN TBG. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2014 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 150 SX CMT WITH 250# HULLS DOWN 5 1/2" CASING. DISPLACE WITH WATER TO 1230'. TEST CASING TO 600#. HOLDING. RAN CBL FROM 1000' TO 10'. TOC AT 70'. RUN TBG TO 1154'. CIRCULATE CMT TO SURFACE WITH 130 SX CMT. TOOH WITH TBG & TOP OFF WITH 25 SX CMT. PUMP 6 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
2684	2699		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed _____

Ken Jehlik
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

NOV 17 2014

CONSERVATION DIVISION
WICHITA, KS

11/25/14 ckm

Form CP-2/3

RECEIVED

NOV 11 2014

KCC DODGE CITY