

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-20435-00-00  
Spot: SE Sec/Twnshp/Rge: 27-23S-31W  
1320 feet from S Section Line, 3960 feet from W Section Line  
Lease Name: STEVENS Well #: 1-27  
County: FINNEY Total Vertical Depth: 2710 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2710	0	WITH 625 SX CMT
SURF	8.625	368		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2014 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/31/2014 2:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

1ST PLUG AT 2710' WITH 200# HULLS & 150 SX CMT. DISPLACE WITH WATER TO 1130'. TEST CASING TO 500#. HELD. RAN CBL FROM 1000' TO 0'. TOC @ 175'. 2ND PLUG RAN TBG TO 1185' & CIRCULATED CMT TO SURFACE WITH 115 SX CMT. TOOH WITH TBG. TOP OFF WITH 15 SX CMT. 3RD PLUG PUMP 10 SX CMT DOWN ANNULUS WITH 200#. HELD.

Perfs:

Top	Bot	Thru	Comments
2663	2673		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed Larry Harris  
(TECHNICIAN)

RECEIVED  
NOV 11 2014  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION  
NOV 17 2014  
CONSERVATION DIVISION  
WICHITA, KS