

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-20501-00-00  
Spot: SWSWNSW Sec/Twnshp/Rge: 22-23S-31W  
1334 feet from S Section Line, 3933 feet from E Section Line  
Lease Name: MERRILL Well #: 1-22  
County: FINNEY Total Vertical Depth: 2711 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2711	0	WITH 650 SX CMT
SURF	8.625	330		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2014 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 100 SX CMT WITH 200# HULLS. DISPLACE WITH WATER TO 1200'. TEST CASING TO 700#. RUN CBL TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/30/2014 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 120 SX CMT WITH 200# HULLS VIA 5 1/2" CASING. DISPLACE WITH WATER TO 1250'. RUN CBL FROM 1000' TO 0'. TOC AT 70'. TIH W/TBG TO 1184'. CIRCULATE CMT TO SURFACE WITH 120 SX CMT. TOOH WITH TBG. TOP OFF WITH 20 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
2655	2665		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed Ken Jehlik (TECHNICIAN)  
11-25-14 CCM

RECEIVED  
NOV 11 2014  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION  
NOV 17 2014  
CONSERVATION DIVISION  
WICHITA, KS