

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-24266-00-00
Spot: NESESWSE Sec/Twnshp/Rge: 16-7S-18W
555 feet from S Section Line, 1405 feet from E Section Line
Lease Name: BIGGE Well #: 16-1
County: ROOKS Total Vertical Depth: 3428 feet

Operator License No.: 32639
Op Name: CORAL PRODUCTION CORPORATION
Address: 1600 STOUT ST STE 1500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
COND		54		70 sx
SURF	8.625	1332		500 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/04/2014 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE
Date/Time Plugging Completed: 11/04/2014 6:45 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

1st plug @3388 w/50 sx
2nd plug @1388 w/50 sx
3rd plug @750 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY

Plugged through: DP

District: 04

Signed Bruce Rodie
11/25/14 CKM (TECHNICIAN) CM

NOV 13 2014

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

NOV 19 2014

CONSERVATION DIVISION
WICHITA, KS