

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40543-00-00
Spot: SENENWSE Sec/Twnshp/Rge: 5-35S-12E
2026 feet from S Section Line, 1327 feet from E Section Line
Lease Name: VENAMON Well #: 6 (17)
County: CHAUTAUQUA Total Vertical Depth: 977 feet

Operator License No.: 30522
Op Name: CORNWELL, LTD.
Address: PO BOX 142
GRENOLA, KS 67346

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	967		30 SX
SURF	10	40		13 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2014 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: BRET TEMPLE Company: _____ Phone: (219) 776-9177

Proposed Plugging Method: run 1" to bottom and circulate gel, spot 5 sks of cement on bottom, circulate cement from 350' to surface, cut off casings below G.L.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 10/02/2014 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 880' gelled hole and spotted 20 sack plug. Pulled 1" out and perforated casing at 650' and 350'. Ran 1" back into 650' and spotted 15 sack plug. Pulled up to 350' and circulated cement to surface inside and outside casing. Pulled 1" and topped well off. A total of 197 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
967	977		
RECEIVED			
NOV 18 2014			
KCC Chanute Dist. #3			
DS			

Remarks: WELL WAS PLUGGED DUE TO AGREEMENT SIGNED BY OPERATOR

Plugged through: TBG

District: 03

Signed _____

11-25-14 CKM

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

NOV 24 2014

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3