

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-20529-00-00  
Spot: NWNW Sec/Twnshp/Rge: 10-23S-22W  
4629 feet from S Section Line, 4724 feet from E Section Line  
Lease Name: QUERBACH Well #: 1  
County: HODGEMAN Total Vertical Depth: 4438 feet

Operator License No.: 32331  
Op Name: DK OPERATING INC.  
Address: 621 BENTON ST.  
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1409		WITH 2 SX CMT
CIBP		4350		WITH 2 SX CMT
PROD	4.5	4433	0	WITH 175 SX CMT
SURF	8.625	1019		WITH 500 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/17/2014 9:00 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-5051

Proposed Plugging Method: SET CIBP @ 4370' & 2 SX CMT. PULL CASING & PLUG WHILE PULLING. PLUG AT 1400' WITH 15 SX GEL & 50 SX CMT. PLUG AT 1030' WITH 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/17/2014 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4350' WITH 2 SX CMT. TRIED TO PULL CASING AND COULDN'T GET ANY STRETCH. LOADED HOLE & RAN A BOND LOG. FOUND CMT FROM 1100' TO SURFACE. SET ANOTHER CIBP @ 1409'. LOADED HOLE WITH FLUID & PRESSURED TO 500#. HELD. RAN TBG TO 1350' & PUMPED 115 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4433	4438	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG


District: 01

RECEIVED

OCT 30 2014

KCC DODGE CITY

Signed



(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

NOV 17 2014

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

11.25.14ckm