

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-079-34919-00-00
Spot: NWSESE Sec/Twnshp/Rge: 18-22S-3W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: NEUFELD Well #: 6
County: HARVEY Total Vertical Depth: 3490 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 211 S FRONT ST
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3489		275 SX
SURF	8.625	497		350 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/25/2014 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (785) 483-4098

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 10/31/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3341' CAPPED WITH 5 SXS CEMENT - SET CIBP @ 3095' CAPPED WITH 2 SXS CEMENT ON TOP. PERFORATED CASING @ 550', RAN TUBING INTO 545' SPOTTED 300 SXS CEMENT # 3% CC, LOST CIRC., LET SET OVERNIGHT, TAGGED TOC @ 715', RAN TUBING INTO 545' CIRCUALTED TO SURFACE WITH 160 SXS CEMENT 3% CC.

Perfs:

Top	Bot	Thru	Comments
3431	3441		
3176	3186		
3141	3143		

Remarks: COPELAND CEMENTING OUT OF GREAT BEND COMMON CEMENT. FAILED TO TAL.

Plugged through: TBG

District: 02

Signed B. J. Hope

Received
KANSAS CORPORATION COMMISSION

11.25.14 ckm (TECHNICIAN)

NOV 21 2014

CONSERVATION DIVISION
WICHITA, KS

JK