

TO:

API Well Number: 15-111-20525-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

Spot: NESWNWSE Sec/Twnshp/Rge: 13-21S-10E
1751 feet from S Section Line, 3033 feet from W Section Line
Lease Name: FRANCIS REDEKER Well #: 3
County: LYON Total Vertical Depth: 2617 feet

Operator License No.: 32044

Op Name: TRIMBLE & MACLASKEY OIL LLC

Address: 110 SOUTH ST PO BOX 171
GRIDLEY, KS 66852

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/03/2014 9:00 AM

Plug Co. License No.:

Plug Co. Name:

Proposal Rcvd. from:

Company:

Phone:

Proposed Plugging Method: 50' cement plug @ 2607' 50' cement @ 1300' 150' cement plug to surface

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: NONE

Date/Time Plugging Completed: 11/03/2014 1:30 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

connect to drill pipe, pumped 25 sxs cement, pulled pipe to 1300' pumped 15 sxs cement, pulled pipe to 180' pumped 60 sxs cement to surface.

RECEIVED

NOV 13 2014

KCC Chanute Dist. #3

MH

Remarks:

Plugged through: DP

District: 03

Signed Mick AD
11/25/14 ACM (TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

NOV 17 2014

CONSERVATION DIVISION
WICHITA, KS

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561

ELITE
 CEMENTING & ACID SERVICE, LLC

~~15-111-20525-0000~~
Cement or Acid Field Report
 Ticket No. **1937**
 Foreman E Russell McLeay
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
11-3-14	1.060	Francis Redeker #3	13	21 S	10 E	LYON	KS	
Customer <u>Trimble + MacLasky</u>			Unit #		Driver		Unit #	Driver
Mailing Address <u>P.O. Box 171</u>			105		SHANNON			
City <u>Gridley</u>			113		DAVE			
State <u>KS</u>								
Zip Code <u>66852</u>								

Job Type P.T.A Hole Depth 2617' Slurry Vol. 30 Bbl Tubing _____
 Casing Depth _____ Hole Size 7 7/8 Slurry Wt. 13.5 Drill Pipe 4 1/2
 Casing Size & Wt. _____ Cement Left in Casing _____ Water Gal/SK 6.5 Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting Plug Down Drill Pipe 25 SKs 2607'
15 SKs 1300
60 SKs 180' to Surface
15 SKs Rathole
115 SKs TOTAL

THANKS
Russell McLeay

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-103	1	Pump Charge	1050.00	1050.00
C-107	30	Mileage	3.95	118.50
C-203	115	SKs 60/40 Poz mix	12.75	1466.25
C-206	400 #	gel = 4%	.20	80.00
C-108	5 tons	Ton Mileage Bulk Truck	345.00	345.00
Received KANSAS CORPORATION COMMISSION NOV 17 2014 CONSERVATION DIVISION WICHITA, KS				
				3,059.75
				Sales Tax

Authorization by Mike Stafford Title Rig Pusher Total _____

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.