

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19548-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 2-26S-4E
693 feet from S Section Line, 2162 feet from E Section Line
Lease Name: PAULSON A Well #: 32
County: BUTLER Total Vertical Depth: 1670 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	10	505		
PROD	5.5	1638		50 SX
SURF	6.625	1285		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/07/2014 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS/ CEMENT BACK @ 1580', CIRC 250'-0' 60/44 POZMIX.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/07/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 1650', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 50 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. LAYED TUBING DOWN. TAGGED CEMENT @ 1281'. PRESSURED CASING @ 500#, HELD OK. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 270'-271', 4 HOLES. SWEDGED INTO 5 1/2" CASING CONSOLIDATED MIXED & PUMPED 250 SXS 60/40 POZMIX 4% GEL. CEMENT CIRCUALTED.

Perfs:

Top	Bot	Thru	Comments
1638	1670	CSG	

Remarks: CONSOLIDATED CEMENT TICKET #4647.

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

NOV 12 2014

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

DUANE KRUEGER

11/25/14 CPM

(TECHNICIAN)

✓