

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40451-00-00
Spot: SWSENWNW Sec/Twnshp/Rge: 32-25S-5E
4105 feet from S Section Line, 4561 feet from E Section Line
Lease Name: KIRKPATRICK Well #: 48
County: BUTLER Total Vertical Depth: 671 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	5.5	585		
PROD	6.625	602		0 SX
SURF	8.25	72		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/06/2014 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Revd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS / CEMENT BACK @ 550', CIRC 250'-0' 60/44 POZMIX.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/06/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 308', HIT PARTED TBG SOLID. LAYED DOWN TUBING. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 270' - 271' 4 HOLES. SWEDGED INTO 6.625" CASING, ESTABLISHED CIRCULATION BETWEEN ALL STRINGS & ON BACKSIDE OF 8.25" SURFACE. CONSOLIDATED MIXED & PUMPED 215 SXS 60/40 POZMIX 4% GEL 2% CC. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
645	665	CSG	

Received
KANSAS CORPORATION COMMISSION

Remarks: CONSOLIDATED CEMENT TICKET #46454.

Plugged through: TBG

NOV 12 2014

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed Duane Krueger
11/25/14 CKM (TECHNICIAN)

VJK