

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40452-00-00
Spot: SENESWNW Sec/Twnshp/Rge: 32-25S-5E
3417 feet from S Section Line, 4117 feet from E Section Line
Lease Name: KIRKPATRICK Well #: 35
County: BUTLER Total Vertical Depth: 676 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	10	21		
LI	4.5	642		
PROD	6.625	613		0 SX
SURF	8.25	103		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/06/2014 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS/ CEMENT BACK @ 500', CIRC 250'-0' 60/44 POZMIX

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/07/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 645', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 35 SXS CLASS A COMMON 3.5% CC & DISPLACED IN CASING. LAYED TUBING DOWN. SDON. 8-8-2014, TAGGED CEMENT @ 500'. PRESSURED CASING @ 300#, HELD OK. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 270'-271'; 4 HOLES. RIH W/TBG @ 310', CONSOLIDATED MIXED & PUMPED 60 SXS 60/40 POZIX 4% GEL 2% CC TO SURFACE. LAYED DOWN TUBING. LAYED DOWN 25' 4 1/2" CASING. SWEDGED INTO 7" CASING CONSOLIDATED MIXED & PUMPED 70 SXS 60/40 POZMIX 4% GEL, SHUT IN 1500#. CEMENT CIRCUALTED.

Perfs:

Top	Bot	Thru	Comments
660	676	CSG	
555	560	CSG	

Received
KANSAS CORPORATION COMMISSION

NOV 12 2014

CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED CEMENT TICKET #46453 & 46456.

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
11/25/14 (TECHNICIAN)

1/2