

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-40453-00-00  
Spot: NWSWSENW Sec/Twnshp/Rge: 32-25S-5E  
3140 feet from S Section Line, 3909 feet from E Section Line  
Lease Name: KIRKPATRICK Well #: 6-W  
County: BUTLER Total Vertical Depth: 658 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	622		50 SX
SURF	7	88		45 SX

Well Type: EOR UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/06/2014 8:00 AM  
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.  
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS/ CEMENT BACK @ 570', CIRC 250'-0-. 60/44 POZMIX

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/06/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 582', HIT SOLID. CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. LAYED DOWN TBG @310', REVERSED CIRCULATED HOLE CLEAN (310'-0'). WAITED 2 HRS TAGGED CEMENT @ 333'. PRESSURED CASING @ 300#. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 270' - 271' 4 HOLES. SWEDGED INTO 4 1/2" CASING, CONSOLIDATED MIXED & PUMPED 60 SXS 60/40 POXMIX GEL 2% CC. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
622	658		CSG

Received  
KANSAS CORPORATION COMMISSION

Remarks: CONSOILDATED CEMENT TICKET #46453.

Plugged through: TBG

NOV 12 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed Duane Krueger  
CC: UIC (TECHNICIAN)

11/25/14 CKM

JK