

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-40458-00-00  
Spot: NWSENWSW Sec/Twnshp/Rge: 32-25S-5E  
1709 feet from S Section Line, 4541 feet from E Section Line  
Lease Name: KIRKPATRICK Well #: 4W  
County: BUTLER Total Vertical Depth: 661 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	630		50 SX
SURF	7	84		45 SX

Well Type: EOR UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/09/2014 8:00 AM  
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.  
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/09/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 635', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. LAYED DOWN TBG @ 310', REVERSED CIRCULATED HOLE CLEAN (310'-0'). WAITED 2 HOURS TAGGED CEMENT @ 315'. PRESSURED CASING @ 300#. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 270'-271' 4 HOLES. SWEDGED INTO 4 1/2" CASING, CONSOLIDATED MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL 2% CC. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
630	661	OH	

Received  
KANSAS CORPORATION COMMISSION

Remarks: CONSOLIDATED CEMENT TICKET #48635.

Plugged through:

NOV 12 2014  
CONSERVATION DIVISION  
WICHITA, KS

District: 02 Signed Duane Krueger  
(TECHNICIAN)

cc: uic  
11/25/14 acm

1/4