

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40459-00-00
Spot: NWNENWSW Sec/Twnshp/Rge: 32-25S-5E
2499 feet from S Section Line, 4609 feet from E Section Line
Lease Name: KIRKPATRICK Well #: 8W
County: BUTLER Total Vertical Depth: 666 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	635		50 SX
SURF	7	91		50 SX

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 09/09/2014 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/09/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 610', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION AND MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. LAYED DOWN TUBING @ 310', REVERSED CIRCUALTED HOLE CLEAN (310' -0') WAITED 2 HOURS TAGGED CEMENT @ 320'. PRESSURED CASING @ 300#. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 270'-271' 4 HOLES. SWEDGED INTO 4 1/2" CASING, CONSOLIDATED MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL 2% CC. CEMENT CIRCUALTED.

Perfs:

Top	Bot	Thru	Comments
635	666	OH	

Received
KANSAS CORPORATION COMMISSION

Remarks: CONSOLIDATED CEMENT TICKET #48636.

NOV 12 2014

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed Duane Krueger
(TECHNICIAN)

cc: uic
11/25/14 ckm

JK