

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-06252-00-01
Spot: SESWSW Sec/Twnshp/Rge: 19-12S-15W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: RUSCHA Well #: 5
County: RUSSELL Total Vertical Depth: 3345 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3315		250 SX
SURF	8.625	980		450 SX

Well Type: EOR UIC Docket No: E13057.1 Date/Time to Plug: 11/06/2014 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORP. Phone: (785) 885-8240

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement, 500 # hulls and 10 sx gel.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2014 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1450', 990' and 350'. Ran tubing to 3007' and pumped 8 sx gel followed by 80 sx cement w/100 # hulls. Both braden head and backside were circulating fluids. Pulled tubing to 1519' and pumped 280 sx cement. Fluids circulated from braden head and backside. Pulled tubing to 416' and pumped 65 sx cement. Cement circulated out backside. POOH. Hooked to braden head and pumped a total of 50 sx cement. Circulated cement out of the 5 1/2" casing. Shut in both sides.

GPS: 38.98813 -099.3539

Perfs:

Top	Bot	Thru	Comments
3315	3319		
3305	3310		
3038	3257		
2966	2973		

Remarks: ALLIED CEMENTING TICKET # 65129

Plugged through: TBG

District: 04

Signed Ray A Dinkel
11/25/14 CKM (TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION cc: uic

NOV 19 2014

CONSERVATION DIVISION
WICHITA, KS