

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-21618-00-00
Spot: E2SW Sec/Twnshp/Rge: 19-12S-15W
1320 feet from S Section Line, 3960 feet from E Section Line
Lease Name: RUSCH AB Well #: 1
County: RUSSELL Total Vertical Depth: 3360 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3359		150 SX
SURF	8.625	164		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2014 9:30 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Revd. from: JOEL STULL Company: VESS OIL CORP. Phone: (785) 885-8240

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2014 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 150, 990' and 1450'. CIBP plug set at 3308' in 2004. Ran tubing to 2300' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1300' and pumped 115 sx cement. Cement circulated. POOH. Topped off w/25 sx cement and stayed full. Shut in. Hooked to braden head and pressured up to 350 psi. Vess Oil Office record showed an FO tool (Haliburton port collar) in well, but could not find cement report.

GPS: 38.99086 -099.03220

Perfs:

Remarks: ALLIED CEMENTING TICKET # 55582

Plugged through: TBG

District: 04

Signed Ray A Dinkel
11/25/14 CCM (TECHNICIAN) CM

Received
KANSAS CORPORATION COMMISSION

NOV 19 2014

CONSERVATION DIVISION
WICHITA, KS

NOV 10 2014

Form CP-2/3