

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-00254-00-01

Spot: N2NESWNW

Sec/Twnshp/Rge: 32-31S-5E

3749 feet from S Section Line, 4329 feet from E Section Line

Lease Name: LUMBERT

Well #: 2

County: COWLEY

Total Vertical Depth: 2532 feet

Operator License No.: 33376

Op Name: WILCOX OIL, LLC

Address: 13206 W. NANTUCKET ST.
WICHITA, KS 67235

String Size Depth (ft) Pulled (ft) Comments

CIBP 2020

PROD 4.5 2532 350 SX

SURF 8.625 213 175 SX

Well Type: SWD

UIC Docket No: D23118.0

Date/Time to Plug: 09/15/2014 8:00 AM

Plug Co. License No.: 31539

Plug Co. Name: SAMS WELL SERVICE, INC.

Proposal Rcvd. from: TROY PHILLIPS

Company: WILCOX OIL

Phone: (316) 304-7074

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/15/2014 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG CIRCULATING VARIOUS BRIDGES @1949', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 2% CC & DISPLACED IN CASING. TAGGED PLUG @ 1680'. RIH W/ TBG @ 873', CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 2% CC AND DISPLACED IN CASING. LAYED TBG DOWN @ 310', REVERSED CIRCUALTED HOLE CLEAN (310'-0'). TAGGED CEMENT @ 310'. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 300' - 301' (4 HOLES). SWEDGED INTO 4 1/2" CASING, CONSOLIDATED MIXED & PUMPED 205 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #46475.

Perfs:

Top	Bot	Thru	Comments
1944	1956	CSG	

Received
KANSAS CORPORATION COMMISSION

Remarks: COMPLIANCE/FAILED MIT

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

CC:uic
11/25/14 cfm

NOV 12 2014
CONSERVATION DIVISION
WICHITA, KS