

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-21546-00-01  
Spot: SWSWNW Sec/Twnshp/Rge: 16-16S-29W  
3134 feet from S Section Line, 4652 feet from E Section Line  
Lease Name: KERKHOFF Well #: 1  
County: LANE Total Vertical Depth: 4500 feet

Operator License No.: 7775  
Op Name: WILTON PETROLEUM, INC.  
Address: PO BOX 391  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4000		WITH 2 SX CMT
PROD	4.5	4496	0	WITH 175 SX CMT
SURF	8.625	328		WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/06/2014 11:00 AM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: SET CIBP @ 4000' WITH 2 SX CMT. RUN TBG TO 2220' & CIRCULATE TO 0'. CHECK BACKSIDE TO 600#.

Plugging Proposal Received By: KENNY SULLIVAN  
Date/Time Plugging Completed: 11/06/2014 4:50 PM

Witness Type: COMPLETE (100%)  
KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4000' WITH 2 SX CMT. RAN TBG TO 2220' & CIRCULATED CMT TO SURFACE WITH 165 SX CMT. PULLED TBG & TOPPED OFF WITH 30 SX CMT. PRESSURED THE BACKSIDE TO 600# WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4076	4080		
4050	4054		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

NOV 17 2014

CONSERVATION DIVISION  
WICHITA, KS

RECEIVED

NOV 11 2014

KCC DODGE CITY

Form CP-2/3