

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-21719-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 13-16S-30W  
2310 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: ROEMER TRUST Well #: 1  
County: LANE Total Vertical Depth: 4466 feet

Operator License No.: 7775  
Op Name: WILTON PETROLEUM, INC.  
Address: PO BOX 391  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3868		WITH 2 SX CMT
CIBP		4165		
MSCC		2265		WITH 200 SX CMT
PROD	5.5	4466	0	WITH 200 SX CMT
SURF	8.625	235		WITH 160 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/06/2014 4:00 PM

Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.

Proposal Revd. from: Company: Phone:

Proposed Plugging Method: SET CIBP @ 4000' WITH 2 SX CMT. RUN TBG TO 2220' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE TO 600# WITH CMT.

Plugging Proposal Received By: LARRY HARRIS  
Date/Time Plugging Completed: 11/06/2014 6:00 PM

WitnessType: NONE  
KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 3868' WITH 2 SX CMT. RAN TBG TO 2220' & CIRCULATE CMT TO SURFACE WITH 200 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT. PRESSURED THE BACKSIDE TO 600# WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4451	4461		
4243	4246		
4179	4182		
4130	4134		
3978	3984		
3918	3921		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED  
NOV 11 2014  
KCC DODGE CITY

Signed Larry Harris  
Received  
KANSAS CORPORATION COMMISSION (TECHNICIAN)  
NOV 17 2014  
CONSERVATION DIVISION  
WICHITA, KS

11/25/14 CKM  
Form CP-2/3