

1050232

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-187-20,363-0000

C NW SE, SEC. 36, T 29S, R. 42 W2E

1980 feet from N/S section line

1980 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7339

Lease Name Wilkerson Farms Well # 1-36

Operator: Santa Fe Energy Company

County Stanton

Name & Address William Center Tower I

Well Total Depth 6510 211.58 feet

One West Third, Suite 500

Conductor Pipe: Size _____ feet

Tulsa, OK 74103

Surface Casing: Size 8 5/8 feet 1656

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sage Drilling Company, Inc. License Number 5421

Address 202 South St. Francis, Wichita, KS 67202

Company to plug at: Hour: 11:00 pm Day: 1 Month: June Year: 19 84

Plugging proposal received from Owen Darnell

(company name) Santa Fe Energy (phone) 918-582-6944

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1700' with 50 sx cement

2nd plug at 850' with 40 sx cement
solid bridge

3rd plug bulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:20 am Day: 2 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1700' with 50 sx cement, 2nd plug at 850' with 40

sx cement, 3rd & 4th plugs - solid bridge - bulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to

circulate mouse hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 07 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Western 71543

(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
(if not) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 6-12-84

INV. NO. 1960