

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 30 1964

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Clyde Merckle of D. R. Lauck Drilling Co. has this
 date requested permission to plug the following described well:

Mr. Merckle guarantees payment of the plugging fee.

Operator's full Name: Richard Bohanon

Complete Address: 1405 Liberty Bank, Oklahoma City, Oklahoma

Lease Name: Rolf Well No. # 1

Location: C NE NW Sec. 23 Twp. 27 Rge. 13 (E) (W) W

County Pratt Total Depth 4525 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Merckle was instructed to plug the well as follows:

298' of 8 5/8" surface pipe, cemented with 225 sacks. Fill
hole with drilling mud to 240', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving