

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Richard Bohanon

Complete Address: 1405 Liberty Bank, Oklahoma City, Oklahoma

Lease Name Rolf Well No. # 1

Location C NE NW Sec. 23 Twp. 27 Rge. 13 (E) (W) W

County Pratt Total Depth 4525

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: D. R. Lauck Drilling Company Inc.

Address: 301 South Broadway, Wichita, Kansas License No.

Operation Completed: Hour 8:30AM Day 27th Month Nov. Year 1964

The Above well was plugged as follows:

298' of 8 5/8" surface pipe, cemented with 225 sacks. Fluid level in
the hole was at 115'. 1st cementing plug and 1/4 sack of hulls was push-
ed in fluid to 240', and cemented with 25 sacks, through the drill pipe.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 12/2/64

INV. NO. 254w

Signed: Archie Elving
Well Plugging Supervisor