

15-009-20795-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 9 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Icer Addis

Complete Address Box 8038, Wichita, Kansas 67202

Lease Name Bryant Well No. # 1

Location NE NE NW Sec. 7 Twp. 19 Rge. 12(E) (W)W

County Barton Total Depth 3445

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Company

Address 1105 Williams, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 5:00 A.M. Day 5 Month 4 Year 1974

The above well was plugged as follows:

8 5/8" csg. 205' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 50 sax cement thru drill pipe. Mud to 180' & displaced 25 sax cement thru drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with Halliburton Cementing Company's pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Linn  
Well Plugging Supervisor

DATE 4/9/74

INV. NO. 8903-W