

To: 1-080197 11-10
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-055-21,246-00-00
NE NW NE, SEC. 2, T. 23 S, R. 31 W/X
330 feet from N & section line
1700 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9883
Operator: Sharon Resources, Inc.
Name:
Address 5995 Greenwood Plaza Blvd., Ste. 220
Englewood, CO 80111

Lease Name Carr Well # 2-5
County Finney
Well Total Depth 4900 ^{159.25} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 424

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 1 a.m. Day: 10 Month: 11 Year: 1993

Plugging proposal received from Judy

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2057-78'

1st plug at 2150' with 50 sx cement, 2nd plug at 1400' with 50 sx cement,

3rd plug at 750' with 50 sx cement, 4th plug at 450' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:30 a.m. Day: 10 Month: 11 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement,

2nd plug at 1400' with 50 sx cement,

3rd plug at 750' with 50 sx cement,

4th plug at 450' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/70 Pozmix 6% gel 1/2# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

DATE 11-12-93 did not observe this plugging.

INVOICED
NOV 23 1993
DATE 11-12-93
NO. NO. 39296

Signed Case Morris
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1993
11-12-93
CONSERVATION DIVISION
Wichita, Kansas

EFFECTIVE DATE: 9-22-93

DISTRICT # 1

36A7 Yes No

State of Kansas

NOTICE OF INTENTION TO DRILL 055-21,246-0000

FORM MUST BE TYPED

FORM MUST BE SIGNED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date October 15 1993

Spot NE-NW-NE Sec 2 Twp 23 S Rg 31 East

OPERATOR: License # 9883 Sharon Resources, Inc. 5995 Greenwood Plaza Blvd #220 Englewood, CO 80111 Blaine Day (303) 694-4920

330 feet from North line of Section 1700 feet from East line of Section IS SECTION X REGULAR IRREGULAR

County: Finney Lease Name: Cary Well #: 2-5 Field Name: Stewart

CONTRACTOR: License # Hadvice prior to spud and of A.C.O-1

Is this a Prorated/Spaced Field? yes no Target Formation(s): Mississippian Nearest lease or unit boundary: 330 Ground Surface Elevation: 2879

Well Drilled For: Well Class: Type Equipment: Oil Enh Rec Infield Mud Rotary Gas Storage Pool Ext Air Rotary OWD Disposal Wildcat Cable Seismic # of Holes Other

Water well within one-quarter mile: yes no Public water supply well within one mile: yes no Depth to bottom of fresh water: 150 Depth to bottom of usable water: 1300

If OWD: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Surface Pipe by Alternate: 1 Length of Surface Pipe Planned to be set: (450) 200 Length of Conductor pipe required: N/A Projected Total Depth: 4900

Directional, Deviated or Horizontal wellbores? yes no If yes, true vertical depth: Bottom Hole Location:

Formation at Total Depth: St. Louis Water Source for Drilling Operations: well farm pond other DWR Permit #: N/A Will Cares Be Taken? yes no If yes, proposed zone:

Exp. 3/17/94

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 57-101, et. seq. It is agreed that the following minimum requirements will be met:

usher Judy W/W-E INIT. SPD 11-1-93 LENGTH SURFACE PLANNED 450 of 878 RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. ATHOLED AHEAD? Y N SIZE HOLE URFACE PIPE 8 3/4 @ 424 CONDUCTOR ANHYDRITE T-2057 B-2078 ELEVATION TD 4900 FORMATION RAN PIPE @ DV TOOL SX ALT II DONE Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 2150 Ft. W/ 50 SX 1/2 Base Anyh. @ 1400 Ft. W/ 50 SX 1/2, 1/2 Plug @ 750 Ft. W/ 50 SX Bottom Surface @ 450 Ft. W/ 50 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN C.R. DATE 11-3-93 TYPE OF CEMENT 60/40 67 1/4 FS. STARTING TIME 8:02 (AM/PM) DATE 11-10-93 COMPLETION TIME 11:12 (AM/PM) DATE 11-10-93 RECEIVED NOV 12 1993 CONSERVATION DIVISION Wichita, Kansas