

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

## WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Pratt SEC. 17 TWP. 27S RGE. 13W-E/W  
Location as in quarters or footage from lines:

300' E of C-NW SE


Lease Owner Cinco Exploration Co.

Lease Name Pratt County Airport Well No. 1

Office Address P. O. Box 3723, Victoria, Texas 77901

Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole

Date Well Completed January 26, 1981

Application for plugging filed Verbal Application

Plugging commenced January 26, 1981

Plugging completed January 26, 1981

Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Morris Leslie

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4,560'

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10-3/4"	427'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,560 ft. (rotary total depth) to 600 ft. Set plug at 600 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 600 ft. to 425 ft. Set plug at 425 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 425 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 10 sacks cement in rat hole and 1 sack cement in water well.

Plugging operations accomplished utilizing Halliburton Oil well cementing pump truck through 4½ inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services  
410 Union Center Bldg., Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary Younger, Agent ~~XXXXXX of owner XXXXXXXX of operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Gary Younger*

251 N. Water-Suite 10, Wichita, KS  
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 2nd day of February, 19 81.

*Elsie Willison*  
Elsie Willison - Notary Public.

My Commission expires: July 25, 1982

STATE

FEB - 9 1981

CONSERVATION DIVISION  
Wichita, Kansas

2-9-81

## KANSAS DRILLERS LOG

COMPANY Cinco Exploration Co.

SEC. 17 T. 27S R. 13W

FARM Pratt County Airport No. 1

LOC. 300' E of C-NW SE

COUNTY Pratt

ROTARY TOTAL DEPTH 4,560'

COMM. January 17, 1981 COMP. January 26, 1981

CONTRACTOR H-30, INC. (Rig #3)

ISSUED February 2, 1981

## CASING

10 3/4" Set at 427' cemented w/400 sxs cement

8 5/8"

5 1/2"

4 1/2"

ELEVATION 1,960' K.B

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	226'
Red Bed	320'
Red Bed and Shale	428'
Red Bed	1,285'
Shale and Shells	1,843'
Shale and Lime	2,303'
Lime and Shale	2,535'
Shale and Lime	2,775'
Lime and Shale	3,180'
Shale and Lime	3,440'
Lime and Shale	4,560'
Rotary Total Depth	4,560'


I hereby certify the above and foregoing to be a  
true and correct log of the above described well  
as shown by the drilling reports.

H-30, INC.

  
Gary Younger - V. President

State of Kansas       )  
                              ) ss:  
County of Sedgwick )

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 2nd day of  
February, 1981.

  
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

STAMP: FEB - 9 1981  
CONSERVATION DIVISION  
Wichita, Kansas