

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 17 TWP. 27S RGE. 13W E/W
Location as in quarters or footage from lines:

NW NW

Lease Owner Par Petroleum, Inc.
Lease Name Par Petroleum Airport Well No. 1
Office Address Box 280, Liberal, Kansas 67901
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
Date Well Completed March 15, 1981
Application for plugging filed Verbal Application
Plugging commenced March 15, 1981
Plugging completed March 15, 1981
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation _____ Depth to top _____ bottom T.D. 4,550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	380'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,550 ft. (rotary total depth) to 650 ft. Set plug at 650 ft. and cemented with 50 sacks cement.
Filled hole with heavy rotary mud from 650 ft. to 360 ft. Set plug at 360 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 360 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 20 sacks cement, 10 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well Cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary Younger, Agent (~~employee~~ of owner) ~~xxx (owner) xxx operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
251 N. Water Suite 10, Wichita, KS
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 24th day of March, 19 81

Elsie Willison
Elsie Willison - Notary Public.

My Commission expires: July 25, 1982

KANSAS DRILLERS LOG

COMPANY Par Petroleum, Inc.

SEC. 17 T. 27S R. 13W
LOC. NW NW

FARM Par Petroleum Airport No. 1

COUNTY Pratt

ROTARY TOTAL DEPTH 4,550'

COMM. March 6, 1981

COMP. March 15, 1981

CONTRACTOR H-30, INC. (Rig #3)

ISSUED March 24, 1981

CASING

10 3/4" Set at 380' cemented w/325 sxs cement

8 5/8"

ELEVATION 1,967' K.B

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	155'
Red Bed	381'
Red Bed and Shale	1,380'
Shale, Shells, and Lime	2,010'
Shale and Lime	2,185'
Lime and Shale	2,775'
Shale and Lime	3,030'
Lime and Shale	4,474'
Lime	4,550'
Rotary Total Depth	4,550'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Gary Younger

Gary Younger

State of Kansas)
) ss:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 24th day of March, 1981.

RECEIVED
STATE CORPORATION COMMISSION
MAR 31 1981

Elsie Willison

Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982