


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 18 Twp. 27^S Rge. (E) 13 (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines NE NE SW
 Lease Owner Wilkinson Drilling, Inc.
 Lease Name Reschke # 1 Well No. #1
 Office Address 805 Union Center, Wichita 2, Kansas.
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed 1/2/1962
 Application for plugging filed 1/2/1962
 Application for plugging approved 1/2/62
 Plugging commenced 1/2/1962
 Plugging completed 1/2/1962
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Fred Hampel, Pretty Prairie, Kansas.
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
					STATE CORPORATION COMMISSION	
					JAN 9 3 1962	
					CONSERVATION DIVISION	
					Wichita, Kansas	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. First plug set @350' W/20 sacks cement through Drill Pipe. Second plug set @ 35' W/10 sacks cement and 2 or 3 gallons Hulls with each plug. Plug down @ 1:30 PM, 1-2-62

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Wilkinson Drilling, Inc.
 Address 805 Union Center, Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Walter M. Wilkinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter M. Wilkinson
805 Union Center, Wichita 2, Kansas.
 (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 19 62

Carolyn K. Iverson
 Carolyn K. Iverson Notary Public.

My commission expires January 2, 1965



January 17, 1962

Wilkinson Drilling, Inc.
Reschke # 1

NE NE SW, Sec. 18-27^S-13^W,
Pratt County, Kansas.

Contractor: Wilkinson Drilling, Inc.
Commenced: December 19, 1961
Completed: January 2, 1962
Elevation: 1976 Kelly Bushing
Casing: 8 5/8" @882' W/250 sacks common cement
225 sacks quick set.
Total Depth: 4553'

FIGURES INDICATE BOTTOMS OF FORMATION

0 - 735	Shale, Sand & Clay
735 - 877	Red Beds & Shale
877 - 900	ANHYDRITE
900 - 1785	Shale & Shells
1785 - 2270	Lime
2270 - 3695	Lime & Shale
3695 - 3849	Shale, Lime & Sandy Shale
3849 - 4190	Lime & Shale Streaks
4190 - 4326	Shale & Lime
4326 - 4402	Chert, Shale & Lime
4402 - 4432	Shale & Sand Stringers
4432 - 4443	Sand
4443 - 4446	Shale
4446 - 4451	Sand
4451 - 4521	Shale & Sand Stringers
4521 - 4553	ARBUCKLE Dolomite

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1962

CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the driller's log on the Reschke #1, located NE NE SW of Section 18-27^S-13^W, Pratt County, Kansas.

WILKINSON DRILLING, INC.

Walter M. Wilkinson
Walter M. Wilkinson

Subscribed and sworn to before me this 17th day of January, 1962.

Carolyn K. Iverson
Carolyn K. Iverson

My commission expires: January 2, 1965.