

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-009-61645-0000
WELL PLUGGING RECORD

Barton County. Sec. 7 Twp. 19 Rge. XEX12 (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner ALPINE OIL & ROYALTY CO., INC.

Lease Name Hammeke Well No. B-1

Office Address 1100 Biting Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 9, 19 53

Application for plugging filed March 9, 19 53

Application for plugging approved March 9, 19 53

Plugging commenced March 9, 19 53

Plugging completed March 9, 19 53

Reason for abandonment of well or producing formation not productive

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3464' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	230'	cemented
				5 1/2"	3452'	pulled
						1534'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Solid plug at 3222'. Sand from 3222' to 3150' and five sacks cement. Heavy mud from 3125' to 240'. Rock bridge 240-230'. 25 sacks cement with dump bailer. Heavy mud to 30'. 10 sacks cement to base of celler.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor QUAKER DRILLING CO., INC.

Address 1100 Biting Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul

1100 Biting Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of March, 19 52

My commission expires Sept. 14, 1953

RECEIVED
STATE CORPORATION COMMISSION Notary Public.
RWO

MAR 23 1953
CONSERVATION DIVISION
03-23-53

PLUGGING
FILE SEC 7 T 19 R 213
BOOK PAGE 83 LINE 31

