


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

15-009-01649-0000  
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County, Sec. 7 Twp. 19S Rge. 12W (E) (W)  
Location as "NE/CNW/KSWK" or footage from lines SW SW SE  
Lease Owner Alpine Oil & Royalty Co., Inc.  
Lease Name Hammeke Well No. A-2  
Office Address 1100 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 4-4 19 52  
Application for plugging filed 12-10 19 54  
Application for plugging approved 12-10 19 54  
Plugging commenced 1-14 19 55  
Plugging completed 1-22 19 55  
Reason for abandonment of well or producing formation Non-productive

If a producing well is abandoned, date of last production 12-13 19 54  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner  
Producing formation Lansing Depth to top 3161 Bottom \_\_\_\_\_ Total Depth of Well 3421 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	211'	cemented
				5 1/2"	3420'	2370'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3421 to 3410 feet Sand bridge  
3410 to 3380 feet 5 sacks cement  
Surface hole squeezed with 15 sacks mud and 85 sacks cement

Name of Plugging Contractor R & S Pipe Pulling Co.  
Address Box 192, Ellinwood, Kansas

STATE OF KANSAS  
CONSERVATION DIVISION  
Wichita, Kansas  
REC'D  
01-29-55

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Thomas M. McCaul (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Thomas M. McCaul  
1100 Bitting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January, 19 55

My commission expires August 10, 1957

Virginia Mendell  
Notary Public.

PLUGGING  
FILE SEC 7-19-R-12W  
BOOK PAGE 83 LINE 12

WELL LOG

ALPINE OIL & ROYALTY CO., INC. Elevation: 1851 R.B.  
Contractor: Quaker Drilling Co., Inc. Commenced: 2-15-52  
Hanneke A-2 Completed: 2-26-52  
SW SW SE Sec. 7-19S-12W  
Barton Co., Ks. Production:

Casing Record:

Set 211' of 8 5/8" with 150 sacks cement

(Figures indicate bottom of formations)

<u>FORMATIONS:</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Clay and Sand	135	Heebner	3039 -1188
Shale and Sand	207	Brown Lime	3146 -1295
Sand	240	Lansing	3161 -1310
Shale and Pyrites	265	Conglomerate	3410 -1559
Shale and Shells	350	Arbuckle	3418 -1567
Shale	715	T.D. (r)	3421 -1570
Anhydrite	737		
Shale and Shells	1250		
Shale and Lime	1900		
Lime	2005	Set 3420' of 5 1/2" With 125 sax.	
Shale and Lime	2625		
Lime	3421 T.D.		

I hereby certify that the above is a true and correct copy of Driller's Log of well drilled in the SW SW SE of Section 7, Township 19 South, Range 12 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. Paul  
President

Subscribed and sworn to before me this 28th day of Feb., 1952.

My Commission Expires:

~~March 7, 1955~~  
Sept. 4, 1953

Vashti Bell  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

JAN 29 1955

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 7 19 R 12W  
BOOK PAGE 83 LINE 10