

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

15-009-30233-0000  
 Form CP-4  
 Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Barton SEC. 7 TWP. 19S RGE. 12W E/W  
 Location as in quarters or footage from lines:  
C-W/2 SE/4 SE/4


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Raymond Oil Company, Inc.  
 Lease Name Hammeke #3 Well No. \_\_\_\_\_  
 Office Address One Main Place Suite 900 Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 5-22-82  
 Plugging completed 5-26-82  
 Reason for abandonment of well or producing formation  
Depleted

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3461'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				9"	200'	none
				5-1/2"	3432'	989'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with sand to 3140' and ran 5 sacks cement. Shot casing @2560'  
and 2420'. Pipe parted 32 joints down. Plugged well with 3 sacks hulls, 10 sacks  
gel, 20 sacks cement, 15 sacks gel, 2 sacks hulls, 130 sacks cement, 50/50 pos,  
4% gel, 3% cc.

Plugging Complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.


RECEIVED  
 STATE CORPORATION COMMISSION

(Signature) R. Darrell Kelso

Box 176 Chase, Ks. 67524  
 (Address)

06-07-82 JUN - 7 1982

SUBSCRIBED AND SWORN TO before me this 4th day of June, 1982



Irene Hoover  
 Notary Public.

My Commission expires: \_\_\_\_\_

RAYMOND OIL COMPANY, INC.  
#3 Hammeke  
C-W/2 SE/4 SE/4 Sec. 7-19S-12W  
Barton County, Kansas

ELEVATION: 1871 KB  
1868 DF  
1866 GL

Contractor: Raymond Oil Company, Inc. Casing Record  
Rig #9 9" @ 200' w/150 sx.  
Commenced: March 3, 1965 5 1/2" @ 3432' w/150 sx.  
Completed: March 12, 1965 (Rotary)

Figures Indicate Bottom of Formation


<u>Formation</u>	<u>Depth</u>
Shale and Sand	100
Shale	239
Pyrite	257
Shale	340
Shale and Sand and Lime	724
Shale and Shells	766
Red Bed and Shale	1010
Shale and Shells	1520
Lime	1821
Lime and Shale	2965
Lime	3022
Lime and Shale	3186
Lime	3461

STATE OF KANSAS )  
 ) SS:  
COUNTY OF SEDGWICK )

I hereby certify that the above is true and correct to the best of my knowledge.

  
Patrick R. Raymond

Subscribed and sworn to before me, this 17th day of March, 1965.

  
Ronnie Donnelly - Notary Public

My commission expires:  
February 15, 1967

RECEIVED  
STATE CORPORATION COMMISSION

APR - 7 1962

CONSERVATION DIVISION  
Wichita, Kansas

