


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. BOX 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barton

County. Sec. 7 Twp. 19 Rge. 12 (E) W (W)

Location as "NE/CNWSW" or footage from lines NE NE NW

Lease Owner Icer Addis

Lease Name BRYANT Well No. 1

Office Address - P.O. Drawer 8038 - Wichita, Ks. 67208

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 5 1974

Application for plugging filed April 5 1974

Application for plugging approved April 5 1974

Plugging commenced April 5 1974

Plugging completed April 5 1974

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation Depth to top Bottom Total Depth of Well 3445' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud.
Bottom plug set at 450' with 50 sacks cement thru drill pipe.
Come up hole to 180' -set plug w/25 sacks cement thru drill pipe
Top plug set at 40', 1/2 sacks hulls, & 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 9 1974
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Duke Drilling Co. (If additional description is necessary, use BACK of this sheet)
Address Box 823 - Great Bend, Ks. 67530

STATE OF Kansas, COUNTY OF Barton, ss.
Larry Curtis (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis

Box 823 - Great Bend, Ks. 67530 (Address)

SUBSCRIBED AND SWORN to before me this 8th day of April 1974.

My commission expires April 11, 1974
Notary Public.

DRILLERS' WELL LOG

DATE COMMENCED: March 28, 1974
 DATE COMPLETED: April 5, 1974

Owner Address
 BRYANT #1
 NE NE NW
 Sec. 7-Twp. 19, Rge 12W
 Barton Co. Kansas

ELEVATION: 1851 K.B.

0 - 205' Shale & Streaks of Sand
 205 - 215' Shale
 215 - 230' Sand
 230 - 280' Shale
 280 - 699' Red Bed
 699 - 726' Anhydrite
 726 - 790' Red Bed
 790 - 1310' Shale
 1310 - 1845' Shale & Lime Steaks
 1845 - 2165' Lime & Shale
 2165 - 2660' Shale
 2660 - 2806' Shale & Lime
 2806 - 3034' Lime
 3034 - 3039' Shale
 3039 - 3054' Lime & Shale
 3054 - 3072' Lime
 3072 - 3140' Shale
 3140 - 3376' Lime
 3376 - 3410' Shale
 3410 - 3430' Conglomerate
 3430 - 3445' Dolomite
 3445' RTD

FORMATION DATA

Anhydrite 699
 Heebner 3034
 Toronto 3054
 Douglas 3072
 Br. Lime 3140
 Kansas City 3153
 Base K.C. 3376
 Conglomerate 3410
 Arbuckle 3430
 RTD 3445

SURFACE CASING: Set used
 8-5/8", 20# casing at 205'
 with 135 sacks 60/40 pozmix,
 2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON (ss)

Larry Curtis of lawful age does swear and state that the facts and
 statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 8 day of APRIL 1974.

My Comm. Expires:
April 11, 1974

Alvin M. Klagge
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 APR 9 - 1974
 CONSERVATION DIVISION
 Wichita, Kansas