

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24224-00-00
Spot: NENWSESW Sec/Twnshp/Rge: 30-6S-18W
1014 feet from S Section Line, 1969 feet from W Section Line
Lease Name: MONGEAU TRUST 'A' Well #: 1-30
County: ROOKS Total Vertical Depth: 3660 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3656		155 SX
SURF	8.625	217		150 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/13/2014 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: MONTE BOYDSTON Company: TRANS PACIFIC OIL CORP. Phone: (785) 650-3138

Proposed Plugging Method:
10/09/2014- Ordered 50 sx 60/40 pozmix 4% gel cement w/100 # hulls.
10/13/2014- Ordered 280 sx 60/40 pozmix 4% gel cement w/200 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2014 4:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

10/09/2014- Operator ran tubing to 3450' and pumped 7 sx gel followed by 50 sx cement w/100 # hulls. Unwitnessed. Pioneer Energy Services shot 4 1/2" casing 2006'. Pulled casing to 1920' and pumped 50 sx cement. Pulled casing to 1600' and pumped 50 sx cement. Pulled casing to 950' and pumped 100 sx cement w/200 # hulls. Pulled casing to 250' and pumped 60 sx cement to circulate cement to surface. Pulled all casing and topped off 8 5/8" surface pipe w/10 sx cement.

GPS: 39.49816N -099.37149W

Remarks: SWIFT SERVICES TICKET # 26891

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

OCT 30 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

11/12/14 ckm

OCT 16 2014