

1060292

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,460-00-00

NW NE NW, SEC. 18, T 27 S, R 13 W
4950 feet from ~~NXX~~ section line
3630 feet from ~~WXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7275

Lease Name Scott Well # 1-A

Operator: Craig/Stephfield Oil & Gas
Name & Address P. O. Box 2646
Ponca City, OK 74602

County Pratt

Well Total Depth 4597 149.40 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Heartland Drilling, Inc. License Number 5867

Address One Main Place, Suite 600, Wichita, KS 67202-1399

Company to plug at: Hour: 4:00 pm Day: 2 Month: August Year: 19 84

Plugging proposal received from Mike Thorpe

(company name) Heartland (phone) 316-265-9723

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4590' with 50 sx cement

2nd plug at 740' with 50 sx cement

3rd plug at 390' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plug water well with 5 sx cement

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:15 pm Day: 2 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4590' with 50 sx cement, 2nd plug at 740' with 50 sx cement, 3rd plug at 390' with 50 sx cement, 4th & 5th plugs - solid bridge- hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement, plugged water well with 5 sx cement.

Remarks: Used 60/40 Pozmix 2% gel by Sun No. 19730
(if additional description is necessary, use BACK of this form)

INVOICED (if not) observe this plugging.

DATE 8-14-84
3083

Signed Paul A. Luthie (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
AUG 07 1984
CONSERVATION DIVISION
Wichita, Kansas