

1 030915

2-12-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-20,394-00-00

NE NE NE, SEC. 18, T 27 S, R 13 W/E

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # N/A

Lease Name Martin Well # 1

Operator: Cobra Drilling

County Pratt 145.41

Name & Address N/A

Well Total Depth 4474 feet

(Note: Bill to Pratt Well Service)

Conductor Pipe: Size _____ feet

Box 847
Pratt, Ks. 67214

Surface Casing: Size 10 3/4 feet 267

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 11 a.m. Day: 12 Month: 2 Year: 19 88

Plugging proposal received from Ken Gates

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 4 1/2" at 4512' 8 5/8" at 952' Perfs at 4443-4'

1st plug sand back to 4341' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls and 125 sx cement down 8 5/8",

3rd plug pump 75 sx ATL cement down 10 3/4".

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour 12:15 p.m. Day: 12 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4341' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, plug, and 125 sx Econolight cement down 8 5/8",

3rd plug pumped 75 sx cement down 10 3/4" annulus.

Shut in 50 psi.

RECEIVED
STATE CORPORATION COMMISSION

FEB 17 1988

Remarks: Used Econolight cement by Halliburton. Recovered 2111' of 12" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (Name & Address) observe this plugging.

Signed Steve Churant
(TECHNICIAN)

DATE 2-18-88

INV. NO. 19887

2-12

MAR 24 1988

AUG 26 1988