

6 061062

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-009-20,559 0000  
SE, SEC. 7, T. 19 S., R. 12 W. 12  
660 feet from S section line

TECHNICIAN'S PLUGGING REPORT

2310 feet from E section line

Operator License # 5046

Lease Name Hommeke Well # 1-A

Operator: Raymond Oil Co. Inc.

County Barton 112.13

Name & Address Box 48788,

Well Total Depth 3450 feet

Wichita, Ks.

Conductor Pipe: Size \_\_\_\_\_ feet

67201

Surface Casing: Size 9 5/8" feet 205'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, Ks. 67524

Company to plug at: Hour: 12:00 Noon Day: 15 Month: Sept. Year: 1986

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: Order 100 sh. 4 5/8" Formix - 90% Sol. - 2% Exonlit, 5 sh. hulls.

Plugging Proposal Received by John R. Sled  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 PM Day: 15 Month: Sept. Year: 1986

ACTUAL PLUGGING REPORT 9 5/8" - 205' w/ 140 sh. 5 1/2" - 3445' w/ 150 sh.

Top perf C 3202', Plugged bottom w/ sand & 5 sh. cement to 3150'.  
Shot pipe 3 times & recovered 2000'. Pumped in 9 5/8" - 5 sh. hulls,  
100 sh. cement w/ 1000 p.s.i.

Remarks: By Allied RECEIVED

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-22-86

INV. NO. 14998

Signed John R. Sled  
(TECHNICIAN)

9-19-86