

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-153-05216-00-00  
Spot: SESE Sec/Twnshp/Rge: 20-1S-32W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: WILHELM UNIT Well #: 12  
County: RAWLINS Total Vertical Depth: 4177 feet

Operator License No.: 34530  
Op Name: BOW CREEK OIL COMPANY, GENERA  
Address: 1304 EISENHOWER RD.  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4177		125 SX
SURF	7	331		275 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/03/2014 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: TONY STROUP Company: CONSOLIDATED OIL WELL SERVI Phone: (785) 650-1778

Proposed Plugging Method: Tried to wash down well for use as SWD but ran into trouble.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE  
Date/Time Plugging Completed: 07/03/2014 4:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 2500' and pumped 100 sx 60/40 pozmix 4% gel cement w/250 # hulls. Pulled tubing to 1500' and pumped 100 sx cement w/250 # hulls. Pulled tubing to 422' and circulated with 50 sx cement. Topped off w/20 sx cement. Pressured backside to 500 psi.

Perfs:

Top	Bot	Thru	Comments
4133	4142		
4122	4126		
4090	4094		
4076	4080		
3988	3994		
3976	3982		

Remarks: CONSOLIDATED OIL WELL SERVICES TICKET # 46806

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Case Morris*

(TECHNICIAN)

KCC WICHITA

12/11/14 *CKM*

DEC 09 2014

RECEIVED