

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-03228-00-00
Spot: SESESENE Sec/Twnshp/Rge: 16-24S-18E
2740 feet from S Section Line, 150 feet from E Section Line
Lease Name: CLINE Well #: C8
County: ALLEN Total Vertical Depth: 875 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.875	840		0 SX
SURF	8.25	17		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/24/2014 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Revd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: COMPANY SERVICE UNIT RIH 2" 8RD TBG TO BOTTOM. ELITE CEMENTING & ACID SERVICES WILL GEL HOLE TO SURFACE THEN PUMP 300' CMT PLUG ON BOTTOM. SERVICE UNIT PULL TBG UP TO 500' ELITE PUMP 50' CMT PLUG SERVICE UNIT PULL TBG UP TO 250' ELITE PUM P CEMENT FROM 250' TO SURFACE SERVICE UNIT PULL REST OF TBG OUT ELITE TOP WELL OFF. COMPANY WILL GO BACK LATER AND CUT SURFACE OFF"BELOW PLOW DEPTH"

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 10/24/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 2" tubing to 875'. Pumped and spotted 25sacks of portland cement at 875'. Pulled tubing up to 500'. Pumped and spotted 10 sacks of portland cement at 500'. Pulled tubing up to 250'. Pumped and circulated cement from 250' to surface. Pulled the rest of the 2" tubing out of the well. Ran 1" pipe down backside of the 4.5" casing. Pumped and circulated cement through the 1" pipe to surface. Pulled 1" pipe and topped the well off with cement. A total of 115 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
840	875		

RECEIVED
DEC 04 2014
KCC Chanute Dist. #3
RD

Remarks:

Plugged through: TBG

District: 03

Signed _____
12/11/14 ekm (TECHNICIAN)

KCC WICHITA
DEC 08 2014
RECEIVED