

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-20619-00-00
Spot: S2SWNW Sec/Twnshp/Rge: 19-21S-8W
2970 feet from S Section Line, 4620 feet from E Section Line
Lease Name: FITZPATRICK C Well #: 1
County: RICE Total Vertical Depth: 3410 feet

Operator License No.: 5210
Op Name: LEBSACK OIL PRODUCTION INC.
Address: PO BOX 354
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3409	1200	100 SX CMT
SURF	8.625	191		180 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/21/2014 4:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2396

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/21/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3205' - CAPPED WITH 4 SXS CEMENT ON TOP. CUT CASING - PIPE OFF @ 1200' PULLED CASING TO 1153' SPOTTED 35-SXS CEMENT. WAITED 2 HOURS TAGGED TOC @ 767'. PULLED CASING TO 703' SPOTTED 35 SXS CEMENT. PULLED CASING TO 250' AND CIRCUALTED TO SURFACE WITH 125 SXS CEMENT. FELL BACK 28' ADDED 6 SXS CEMENT. 11/24/14.

Perfs:

Top	Bot	Thru	Comments
3321	3327		

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, COMMON CEMENT 3% CC, TICKET #42336

Plugged through: CSG

District: 02

Signed

KCC WICHITA

DEC 04 2014

RECEIVED

B. J. Hope
12/11/14 ckm (TECHNICIAN)