

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-21069-00-00
Spot: S2NWSWNW Sec/Twnshp/Rge: 19-4S-31W
1750 feet from N Section Line, 330 feet from W Section Line
Lease Name: SCHMIDT Well #: 1-19
County: RAWLINS Total Vertical Depth: 4467 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	302		280 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/15/2014 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 11/15/2014 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st plug @2600 w/50 sx
2nd plug @1812 w/100 sx
3rd plug @350 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx


Perfs:

Remarks: ALLIED

Plugged through: DP

District: 04

Signed


(TECHNICIAN)

CM

12/11/14 CKM

KCC WICHITA

DEC 09 2014

RECEIVED

NOV 27 2014