

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-22537-00-01
Spot: SESENW Sec/Twnshp/Rge: 5-11S-18W
2870 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SALINE RIVER GRAZING ASS Well #: 7
County: ELLIS Total Vertical Depth: 1431 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3468		175 SX
SURF	8.625	174		130 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 11/26/2014 1:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: LANCE FELLHOELTER Company: TRANS PACIFIC OIL CORP Phone: (620) 388-2306

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Perforations: 1106' - 1122', 1133' - 1152'.
Well was plugged Sept 1985 by Keng Brown Enterprises, washed down on 03/27/1995 to make a SWD (D-20,269). DKT denied. Well was turned into a Cedar Hill (water supply well)

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/26/2014 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Express Well Service milled on well to 1431' and hit cement. Pulled tubing to remove bit and ran tubing back in hole to 1431'. Quality Cementing rigged to tubing and mixed and pumped 150 sx cement w/200 # hulls to circulate cement up 4 1/5" casing. Pulled tubing. Topped with 15 sx cement. Hole standing full. 8 5/8" surface casing full of cement from previous plugging.

GPS: 39.12514 -099.34335
2831' FSL 2963' FEL
SE SE SE NW

Remarks: QUALITY OILWELL CEMENTING TICKET # 729

Plugged through: TBG

District: 04

Signed
KCC WICHITA



(TECHNICIAN)

CM

DEC 09 2014

RECEIVED

cc:MIC ✓
12/11/14 CKM

DEC 01 2014