

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20179-00-00
Spot: E2SESW Sec/Twnshp/Rge: 16-14S-10W
660 feet from S Section Line, 2310 feet from W Section Line
Lease Name: BAKER Well #: 2
County: ELLSWORTH Total Vertical Depth: 2921 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2795		
PROD	4.5	2921		250 SX
SURF	8.625	249		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/26/2014 10:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUEHLER Company: TRANS PACIFIC OIL CORP Phone: (785) 483-1821

Proposed Plugging Method: AS PER KCC RULES & REGS

KCC WICHITA
DEC 18 2014
RECEIVED

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 11/26/2014 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, TAG PREVIOUSLY SET CIBP @ APPROX. 2790'. PERFORATE AT 1250', 900' AND 300'. RUN TUBING TO 2772' AND PUMP 100 SX'S CEMENT. PULL TUBING TO 1250' AND PUMP 75 SX'S CEMENT - DID CIRCUALTE TO SURFACE. PULL TUBING OUT AND CONNECT ON TO 4.5" CASING AND PUMP 100 SX'S CEMENT - DID CIRCULATE UP SURFACE CASING. USED 285 SX'S CEMENT TOTAL.

Perfs:

Top	Bot	Thru	Comments
2836	2854	CSG	

Remarks: 60-40 POZ, 4% GEL. PERF TECH #12240. QUALITY CEMENT #1353. WELL PLUGGED DUE TO 10 YEAR TA EXPIRATION.

Plugged through:

District: 02

Signed Virgil Clothier
(TECHNICIAN)
12/11/14 OKM